

P.A. Of 1990 On 12/16 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
96 DEC 20 AM 9:31  
PAGE # 391, B/C 4  
BUREAU OF LAND SURVEY  
REGISTERED LAND SURVEYORS

Register of Deeds Stamp & File Number

For corners in

MENOMINEE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 37 N R 26 W  
T R  
T 37 N R 26 W  
T R  
C-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SAME AS CORNER C-13 T37N-R26W

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on Nov. 06, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Hemlock, 10" - N52°E - 20 lks; Sugar, 12" - N15°W - 15 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1852: Original Survey (Sec. Subd.) by Francis Coleman - B.T.'s - Cedar, 10" - S75°E - 16 lks; Cedar, 10" - S34°W - 24 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. nail set in the centerline of county roads running East - West and North. We found that the position of this nail fit very closely with GLO record distances to corners East, West and South. This position also fit well with long standing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N41°E 50.52 feet 0.5' W. of Tel Box
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" S35°E 42.23 feet 1.0' W. of Power Pole
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N45°W 49.43 feet
- Metal Survey Sign Post N45°W 59.9 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 30, 1996