

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>37N</u> R <u>26W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
95 DEC 27 PM 3:32
PAGE # 304 BK 4
BARBARA MCGIBSON
REGISTERED DEEDS
RECORDING DIVISION
LANSING MI 48913
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

(SAME AS E-13 T38N-R26W)

I, William Lenca, in a field survey on Nov 14, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5		4		3		2			1
3											
4	7	8		9		10		11			12
5											
6	18	17		16		15		14			13
7											
8	19	20		21		22		23			24
9											
10	30	29		28		27		26			25
11											
12	31	32		33		34		35			36
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey (Twp. Bdy.) by James H. Mullett - B.T.'s - Hemlock, 12" - N32°W - 47 lks; Cedar, 8" - N59°E - 15 lks. All original evidence has been destroyed by farming activities.
- 1852: Original Survey (Sec. Subd.) by Francis Coleman - B.T.'s - Fir, 10" - S72°E - 06 lks; Cedar, 8" - S30°W - 06 lks. All original evidence has been destroyed by farming activities.
- 1963: L.C.R.C. No. 787, Vol. 3 - recorded by C. C. Lindgren, Survey Chief, Mich. State Hwy Dept., states that he set a 1" iron pin at an existing fence corner. TIES: 7" Ced. - S25E - 14.56' (gone); 4" Ced. - N40W - 22.08' (found); 5" Poplar - N05E - 15.05' (found).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1995 Survey in Section 5, T37N-R26W, we found a 1" diameter x 32" long iron rod at the intersection of ancient fences running South - East & West, along with 2 of the B.T.'s established by Lindgren as noted in part "A". This corner position agrees well with an original terrain call to "swamp edge" 1 chain (66 feet) East (recorded and measured). This corner has been accepted and used by local surveyors for at least 32 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

7" dia. Cedar	N16°E	19.23 feet	Scr. NBT
12" dia. Tamarack	N77°E	36.98 feet	Scr. NBT
5" dia. Cedar	South	16.39 feet	Scr. NBT
8" dia. Cedar	N70°W	37.35 feet	Scr. NBT
Metal Survey Sign Post	West	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 11, 1995