

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37</u> N R <u>26</u> W	<u>E2</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

RECEIVED FOR RECORD  
95 DEC 27 PM 3:32  
PAGE # 307 844  
BARBARA HORTONSON  
REGISTER OF DEEDS  
JENISON MI 49758  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Nov. 14, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5	●	4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Hemlock, 6" - N35°W - 11 lks; Black Ash, 12" - S61°E - 19 lks. All original evidence has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1995 Survey in Section 5, T37N-R26W, we traversed to the NE and SE Corners of said Section, and found that the mile measured 5075.32 feet. This agrees very closely with the GLO record distance of 76.88 chains (5074.08 feet) and C. C. Lindgren's distance (as recorded in L.C.R.C. No. 787 - Vol 3) of 5075.34 feet. We set the corner at a proportional position between the NE and SE Corners of Section 5. The corner position thus established falls in an old logging road, and in line with ancient fences running North and South, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

5" dia. White Ash	N67°E	39.18 feet	Scr. NBT
16" dia. Cedar	S37°E	45.11 feet	Scr. NBT
9" dia. Cedar	S60°W	43.12 feet	Scr. NBT
9" dia. Cedar	N38°W	49.66 feet	Scr. NBT
Metal Survey Sign Post	North	11.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 11, 1995

