

# SURVEY & REMONUMENTATION

APR 24 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Four Corners Under Act 345 of

P.A. of 1990 on DEC 16 1994  
W. Davis RLS

For corners in **COMMISSION**  
**MENOMINEE**  
(County)

Located In: 37N 26W Corner Code # E-6

1. Public Land Survey	T	R							
	T	R							
	T	R							
	T	R							
2. Property Controlling in Section	S	T	R						
	S	T	R						
3. Miscellaneous Property in Sec.	S	T	R						
	S	T	R						

REGISTERED FOR RECORD  
4 DEC 27 AM 10:46  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49859  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

William Lenca Jun 23 1994

I, William Lenca, in a field survey on Jun 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1852: Original Survey by Francis Coleman - B.T.'s - Spruce, 10"- N51°W- 26 lks; Cedar - 06", S52°E - 21 lks - All original evidence for this corner has been destroyed by county road improvements.
- 1980: L.C.R.C. No. 227 recorded by Ewart Muller, RLS No. 15408, states that a 5/8" x 12" re-rod was placed by single proportionate measurement - B.T.'s - 7" Y. Birch - N66°W - 40.65'; 6" Cedar - N43°W - 52.95'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

In a 1982 survey of Section 16, we recovered Muller's 5/8" iron rod and B.T.'s and used this corner and the Southwest corner to establish the Northwest corner of Section 16. In our 1994 survey, we found that Muller's 5/8" iron had been destroyed, but the B.T.'s were still in place. We replaced the corner from the existing B.T.'s and found that this position fit with a single proportionate location between the NW and SW corners. This corner has been used by surveyors over the past 14 years, and is accepted as a careful and faithful re-establishment of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

9" dia. Cedar (Ex. B.T.)	N43°E	52.95 feet	Scr. NBT
8" dia. Ironwood	S57°E	42.34 feet	Scr. NBT
6" dia. Cedar	S47°W	39.92 feet	Scr. NBT
10" dia. Yellow Birch (Ex. B.T.)	N66°W	40.58 feet	Scr. NBT
Survey Sign Post	West	25.0 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date Sep. 15, 1994

Surveyor's Michigan License No. 26461