

# SURVEY & REMONUMENTATION

APR 24 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Fee Group Under Act 345 Of  
P.A. of 1989 On Dec 16 1994  
MEZ DAVIN RLS  
ACTING Register

For corners in  
**COMMISSION**  
**MENOMINEE**  
(County)

Located In:	Corner Code #
1. Public Land Survey T <u>37</u> NR <u>26</u> W	<u>G-4</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	_____
in Section S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
94 DEC 27 AM 10:46  
PAGE # 161 BK 9  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49859  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca in a field survey on Aug. 9, 1994

I, \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 12" - N51°W - 07 lks; Cedar - 12", S45°E - 06 lks - All original evidence for this corner has been destroyed by county road improvements.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

In a 1994 survey of Section 9, we set this corner in the centerline of a North - South County Road, and at a distance halfway between the Northeast Corner and the Southeast Corner of said section. This corner position is accepted as a careful and faithful re-establishment of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 2-1/2" dia. alum. Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

6" dia. Cedar	S75°E	52.22 feet	Scr. NBT
7" dia. Cedar	S23°E	82.70 feet	Scr. NBT
5" dia. White Ash	S44°W	59.57 feet	Scr. NBT
6" dia. Elm	N48°W	38.91 feet	Scr. NBT
Survey Sign Post	East	37.1 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date Sep. 15, 1994  
Surveyor's Michigan License No. 26461