

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On DEC 16 1994

Met. Davis RLS
ACTING

RECEIVED FOR RECORD
DEC 27 AM 10:46
PAGE # 102 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>37N</u> R <u>26W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca

Jun. 22, 1994

I, William Lenca, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Maple, 8" - N70°E - 07 lks; Fir, 10" - S46°W - 11 lks - All original evidence for this corner has been destroyed by county road improvements.

1981: L.C.R.C. No. 291 recorded by William Lenca, RLS No. 26461, states that a 3/4" x 18" Iron Pipe was set in conformance with existing lines of occupation to the North, South and West. B.T.'s - 8" Norway Pine - S60°E - 59.83'; Power Pole - N45°E - 59.81'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1994 survey of Section 16, we recovered the 3/4" x 18" iron pipe and B.T.'s mentioned in part "A". The corner position falls in the centerline of a N-S County Road and 6' South of the centerline of the County Road running West. This position agrees well with existing lines of occupation, and has been relied upon by surveyors for at least 13 years. We accepted the corner location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-1/2" dia. alum. Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

14" dia. White Pine	S62°E	66.23 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. alum. cap - WITNESS MARKER	N46°E	59.73 feet	
5/8" x 24" Iron Rod/2" dia. alum. cap - WITNESS MARKER	S63°W	47.48 feet	
5/8" x 24" Iron Rod/2" dia. alum. cap - WITNESS MARKER	N30°W	64.57 feet	
Survey Sign Post	N30°W	65.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca

Date Sep. 15, 1994

Surveyor's Michigan License No. 26461

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

