

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Mc Davis RLS
 Chairman
 95 DEC 27 PM 3:32
 RECEIVED FOR RECORD
 BARBARA JOHNSON
 REGISTER OF DEEDS
 KENOSHA, WISCONSIN

For corners in
MENOMINEE
 (County)

Located In:	Corner Code #1
37N 26W	L-3
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, William Lenca, in a field survey on July 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25							
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 10" - N76°E - 52 lks; Cedar, 12" - S68°W - 14 lks. All original evidence has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1995 Survey in Section 12, T37N-R26W, we found a P.K. Nail in the centerline of County Roads East - West and South. We found ancient fence lines running North at distances of 1309.7 feet West and 2618.2 feet West from the corner position. The distance East to the Northeast Corner of Section 12 is 2656.25 feet. The position of the existing P.K. Nail fits well with existing lines of occupation, has been used by local surveyors, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N43°E	38.28 feet
Anchor Pole	S43°E	47.36 feet
Power Pole	S53°W	50.34 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N30°W	33.92 feet
Metal Survey Sign Post	N48°E	39.0 feet



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by *William Lenca* Date Nov. 17, 1995
 Surveyor's Michigan License No. 26461