

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In: Corner Code: L-5

- | | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 37N | R | 26W | L-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |

Register of Deeds Stamp & File Number

RECEIVED FOR RECORD
95 DEC 27 PM 3:32
ARAPA MERRISON
REGISTER OF DEEDS
MENOMINEE COUNTY

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca, in a field survey on July 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1852: Original Survey by Francis Coleman - B.T.'s - Sugar Maple, 12" - N68°E - 27 lks; Sugar Maple, 10" - S45°W - 22 lks. All original evidence has been destroyed by farming activities.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1995 Survey in Section 12, T37N-R26W, we found an ancient fence corner at the top of a 70 foot ridge. The original notes indicate that the 1/4 corner between Sections 12 and 13 was set at the "top of hill, 70 feet". The GLO distance from this corner East to the SE Corner of Section 12 is 2663.76 feet (40.36 chains). We found this distance to measure 2653.84 feet. Herb Bierke, a long time resident of the area, stated that the fences at the location of the 1/4 corner were at least 80 years old. Since the position of the ancient fence corner fits GLO terrain calls and existing lines of occupation, we accepted it as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location at ancient fence corner:
- | | | | |
|------------------------|-------|------------|----------|
| 9" dia. Maple | N65°E | 37.85 feet | Scr. NBT |
| 9" dia. Maple | S07°W | 33.93 feet | Scr. NBT |
| 18" dia. Hard Maple | S85°E | 34.61 feet | Scr. NBT |
| 11" dia. Hard Maple | N27°W | 48.78 feet | Scr. NBT |
| Metal Survey Sign Post | West | 1.2 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 17, 1995
Surveyor's Michigan License No. 26461