

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T37N R 25W	A06
	T R	
	T37 R26	M-6
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORDS
 96 OCT -7 PM 3:26
 PAGE # 363 BK 4
 BARBARA HORNISON
 REGISTERED DEEDS
 REGISTERED LAND SURVEYOR
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 SAME AS CORNER M-6 T37N-R26W .

I, William Lenca, in a field survey on May 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Ironwood, 4" - S47°W - 08 lks.; Sugar Maple, 10" - N59°W - 18 lks. No original evidence found - destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Finding no original evidence, or evidence of subsequent restoration, we re-established this corner by single proportionate method between the Northwest Corner (A05) and the Southwest Corner (A07) of Section 18, T37N-R25W. This location fits well with a GLO call to a swamp edge 2 chains south, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

12" dia. Hemlock	S81°E	12.26 feet	Scr. NBT
7" dia. Balsam	S14°W	27.21 feet	Scr. NBT
8" dia. Hemlock	S83°W	21.79 feet	Scr. NBT
10" dia. White Ash	N02°W	39.39 feet	Scr. NBT
Metal Survey Sign Post	South	1.00 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Sep. 24, 1996