

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 9/25 19996
Mike Smith Rus
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located in: Corner Code #

1. Public Land Survey T37N R 26W A08
 T ___ R ___
 T 37 R 26
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SAME AS CORNER M-8 T37N-R26W

RECEIVED FOR RECORD
 96 OCT -7 PM 3:27
 324 BK. 4
 PAGE 9
 BARBARA MORRISON
 REGISTER OF DEEDS
 REGISTER OF DEEDS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on Jun. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Tamarack, 12" - S47°W - 16 lks.; Tamarack, 12" - N30°W - 23 lks. Original evidence destroyed by county road improvements.
 1986: L.C.R.C. No. 743 recorded by William Lenca, RLS No. 26461, states that a Railroad Spike was set proportionately between the NW Cor. of Section 18 & SW Corner of Section 19. Ties: 6" Ced. - N54°E - 54.18'; 9" Tam. - S35°E - 57.97'; 8" Ced. - S41°W - 54.71'; 6" Tam. - N46°W - 46.84'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 We recovered a railroad spike and 4 Bearing Trees marked NBT as described in L.C.R.C. No. 743. (See part "A") The railroad spike was found 5 feet North of the centerline of an East - West County Road (C.R. 374) and at a proportional location between the NW Corner (A-7) and the Southwest Corner (A-9) of Section 19, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

6" dia. Cedar - Ex. B.T.	N54°E	54.18 feet	Scr. NBT
9" dia. Tamarack - Ex. B.T.	S35°E	57.97 feet	Scr. NBT
8" dia. Cedar - Ex. B.T.	S41°W	54.71 feet	Scr. NBT
6" dia. Tamarack - Ex. B.T.	N46°W	46.84 feet	Scr. NBT
Metal Survey Sign post	South	33.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Sep. 24, 1996

264