

P.A. Of 1990 On 9/25, 19996  
Mc Davis RLS  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
(County)

Located in:

Corner Code #

1. Public Land Survey

T37N R. 25W

A09

T R

T37 R26

M-9 ✓

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

RECEIVED FOR RECORD  
96 OCT -7 PM 3:27  
365 BK-4  
BARBARA JOHNSON  
REGISTERED DEEDS  
MEMORIALS DIVISION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SAME AS CORNER M-9 T37N-R26W

I, William Lenca, in a field survey on Jun. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		2
3												
4	7						8			9		10
5												
6	18						17			16		15
7												
8	19						20			21		22
9												
10	30						29			28		27
11												
12	31						32			33		34
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Birch, 16" - S73°W - 13 lks.; Black Ash, 10" - N38°W - 42 lks.  
All original evidence for this corner has been destroyed by fire & logging activities.  
1986: L.C.R.C. No. 743 recorded by William Lenca, RLS No. 26461, states that a 3/4" x 60" Iron/3" Alum. cap was set in place of very old squared wood post found matching GLO terrain calls. Ties: 8" Maple - S12°E - 40.00'; 9" Balsam - West - 17.85'; 20" W. Pine - N20°E - 25.55'; 24" W. Pine - N78°E - 39.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 3/4" diameter aluminum rod/3-1/4" aluminum cap and 4 Bearing Trees as described in L.C.R.C. No. 743 (See part "A"). This corner has been used for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Accepted existing 3/4" x 60" aluminum rod/3-1/4" Alum. cap stamed for corner location:

8" dia. Maple - Ex. B.T.	S12°E	40.00 feet	Scr. B.T.
9" dia. Balsam - Ex. B.T.	West	17.85 feet	Scr. B.T.
20" dia. White Pine - Ex. B.T.	N20°E	25.55 feet	Scr. B.T.
24" dia. White Pine - Ex. B.T.	N78°E	39.00 feet	Scr. B.T.
Metal Survey Sign Post	South	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Sep. 24, 1996

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date \_\_\_\_\_



365