

Approved by Menominee County  
 Land Survey Reestablishment  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 9/25 19996  
*McDonnell RLS*  
 Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE  
 (County)

Located In: Corner Code #

1. Public Land Survey T37N R 25W B01  
 T\_\_\_ R\_\_\_  
 T38R25 B-13  
 T\_\_\_ R\_\_\_

2. Property Controlling in Section S\_\_\_ T\_\_\_ R\_\_\_  
 S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_  
 S\_\_\_ T\_\_\_ R\_\_\_

REGISTERED FOR RECORD  
 95 001 - 7 PH 3-27  
 PAGE # 370 84.4  
 BARBARA MORRISON  
 REGISTERED LAND SURVEYOR  
 MENOMINEE, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

SAME AS CORNER B-13 T38N-R25W .

I, William Lenca, in a field survey on June 11, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1	●											
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Cedar, 6" - N49°E - 07 lks.; Cedar, 12" - N56°W - 19 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 We re-established this corner in the centerline of county roads running North - South and East, and in line with an ancient fence line running West. This position fits reasonably well with the GLO distance to corners 1/2 mile East and West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N43°E	43.53 feet	
7" dia. Tamarack	S66°E	99.94 feet	Scr. NBT
11" dia. Tamarack	S31°W	87.88 feet	Scr. NBT
10" dia. Tamarack	S89°W	68.72 feet	Scr. NBT
Metal Survey Sign Post	N43°E	44.4 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by *William Lenca*  
 Surveyor's Michigan License No. 26461

Date Sep. 24, 1996