

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by _____ County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Dec 16, 1994
Mez Dahn RLS
ACTING Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>38N</u> | R | <u>25W</u> | <u>C-8</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

RECEIVED FOR RECORD
94 DEC 27 AM 10:46
PAGE # 158 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49853
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on Aug. 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1852: Original Survey by George E. Adair - B.T.'s - Tamarack, 10" - N38°E - 44 lks; Tamarack, 7" - S45°W - 22 lks - No original evidence for this corner was found.
 - 1900: A survey of Section 20, T38N-R25W by Albert Haas, County Surveyor, is on record in County Surveyor's Record book in the Menominee County Register of Deeds Office. This survey states that a 4" Cedar Post was set in the location of C-8 from Government B.T.'s. No new B.T.'s are given.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- In a 1994 Survey of Section 19, T38N-R25W, we found the rotted remains of a very old squared cedar post. The position of this post falls within 1 foot of a straight line between Section Corners, matches the GLO distance north to the Section Corner within approximately 1 foot. The distance south to the Section Corner is within 10 feet of the GLO distance. We felt that we had recovered the post set in the 1900 survey, and, since this post was set from original B.T.'s, we accepted the existing cedar post as a careful and faithful perpetuation of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 2-1/2" dia. alum. Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:
- | | | | |
|-----------------------|-------|------------|----------|
| 9" dia. Cedar | N52°E | 9.49 feet | Scr. NBT |
| 8" dia. Cedar | S14°E | 23.41 feet | Scr. NBT |
| 20" dia. White Spruce | S40°W | 16.99 feet | Scr. NBT |
| 9" dia. Cedar | N33°W | 29.27 feet | Scr. NBT |
| Carsonite Marker | N82°W | 1.4 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sep. 15, 1994
Surveyor's Michigan License No. 26461