

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

P.A. of 1990 On 12/27 1996
Mc Davis RLS
Chairman

For corners in

MENOMINEE Located In: Corner Code #
(County)

1. Public Land Survey T 37N R 25W G01
T R
T 38R 25 G-13 ✓
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD
96 DEC 30 AM 9:07
PAGE # 446 8K4
BARBARA MONTGOMERY
REGISTERED CLERK
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
SAME AS CORNER G-13, T38N-R25W

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		10		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, William Lenca, in a field survey on Jun 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Cedar, 14" - N24°E - 17 lks.; Cedar, 9" - N48°W - 07 lks. All original evidence for this corner has been destroyed by farming activities.
- 1852: Original Survey (Sec Subd) by George Adair - B.T.'s - Hemlock, 8" - S30.5°W - 16 lks.; Yellow Birch, 12" - S42°E - 75 lks. All original evidence for this corner has been destroyed by farming activities.
- 1981: Certified Survey No. 226, recorded by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 34, T38N-R25W. The corner monument is described in the legend as a 1" x 24" Iron Pipe set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1 inch diameter iron pipe in line with ancient fences running North - South and East. The position of the iron pipe matches with distances to corners in Section 34, T38N-R25W, as shown in Certified Survey No. 226. This location also matches well with the GLO call to the West Bank of the Cedar River, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

16" dia. Cedar	N33°E	28.99 feet	Scr. NBT
9" dia. Cedar	East	21.06 feet	Scr. NBT
10" dia. Cedar	S03°E	17.82 feet	Scr. NBT
Metal Survey Sign Post	West	1.10 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Dec. 26, 1996
Date _____

446