

# SURVEY & REMONUMENTATION

JAN 09 2001

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990, On 12/22, 2000  
W. J. DAVIDSON  
Chairman

For corners in  
MENOMINEE  
(County)

Located in: Corner Code #

- |                                       |                             |       |       |
|---------------------------------------|-----------------------------|-------|-------|
| 1. Public Land Survey                 | T <u>38</u> N R <u>26</u> W | C-09  |       |
|                                       | T ___ R ___                 | _____ | _____ |
|                                       | T ___ R ___                 | _____ | _____ |
|                                       | T ___ R ___                 | _____ | _____ |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___           | _____ | _____ |
|                                       | S ___ T ___ R ___           | _____ | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___           | _____ | _____ |
|                                       | S ___ T ___ R ___           | _____ | _____ |

Bk. 6 Pg. 203

RECEIVED FOR RECORD  
28 DEC 2000 2:31:31 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Sep. 05, 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by George Adair - B.T.'s - Spruce, 10" - N28°E - 22 lks; Tamarack, 9" - S57°W - 15 lks. All original evidence for this corner has been destroyed by County Road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Railroad Spike in the center of a 4 way County Road intersection. My private records indicate that this Railroad Spike was set for the Section corner position in a 1995 Survey and subdivision of Section 20, T38N-R26W. This position fits well with measurements to corners 1/2 mile East, 1/2 mile West and 1/2 mile North, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N49°E	64.27 feet	@ Survey Sign Post
Base of Steel Post for Stop Sign	S19°E	41.81 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S47°W	49.43 feet	1.4' E. of Power Pole
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N49°W	42.07 feet	1.0' E. of Power Pole
Metal Survey Sign Post	N49°E	64.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Sept. 8, 2000

