

RECORDED

1993

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of

P.A. Of 1990 On 12/29 1993

For corners in

MENOMINEE (County)

Located In:

Corner Code #

- 1. Public Land Survey T 38N R 26W E-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD DEC 29 PM 3:54 BARBARA MORRISON REGISTER OF DEEDS MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, WILLIAM LENCA, in a field survey on December 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Cell (4,9) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL B.T.'s: W. Pine, 34", N51°E, 30 lks W. Birch, 10", S39°W, 19 lks

Original survey by George E. Adair in 1852. All original evidence for this corner has been destroyed by logging and clearing activities.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4 inch outside diameter Iron Pipe and the remains of a rotted wood post on line with a very old fence line to the East of this location. This corner has been used by local surveyors for several years and matches with occupation lines on the interior of Section 9, and is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 3 columns: Monument description, Bearing, Distance. Includes items like 10" dia. Hemlock, 9" dia. Cedar, 6" dia. Maple, 18" dia. Cedar, Metal Survey Sign Post.



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by [Signature] Date December 27, 1993

Surveyor's Michigan License No. 26461