

FEB 11 1998

Approved by Menominee County
Land Survey Reorganization
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/19/97 1297
Mike Davis BLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>38</u> N R <u>27</u> W	<u>1-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED FOR RECORD
 971009 21 PM 3:18
 524 BLS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug. 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3									10				
4	7		8			9		10		11		12	
5													
6	19		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1852: Original Survey by Harvey Mellon - B.T.'s - Hemlock, 18" - N53.5°E - 47 lks.; Cedar, 12" - S65°W - 8 lks. All original evidence for this corner has been destroyed by logging activities.
 - 1976: CERTIFIED SURVEY No. 114 by Robert Perkins, RLS No. 12027, describes this corner as an iron bolt in 4" casing and shows ties to other property corners in the area.
 - 1987: L.C.R.C. No. 749 by William Lenca, RLS No. 26461, erroneously uses a 1-1/2" dia. Iron Pipe - Witnesses: 7" Cherry - S36°W - 64.59'; 1" dia. Iron Pipe - N14°E - 55.40'; Power Pole - S74°E - 177.88'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1987 survey of Section 3, T38N-R27W, we erroneously accepted a 1-1/2 inch diameter iron pipe for this corner location and recorded it in L.C.R.C. No. 749. In surveying the Hermansville Industrial Site in 1991, we retraced Robert Perkins 1976 Survey (Certified Survey No. 114) and found a 1-1/4 inch square head iron bolt in a 4 inch iron casing matching ties to other corners in this survey. This monument matches with one found at the North Quarter Corner of Section 11, having been placed by Wisconsin Land & Lumber Company. The iron bolt and casing have since been destroyed, however we replaced the corner position from information contained in Certified survey No. 114 and Certified Survey No. 740, and accepted this location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

7" dia. Cherry	S59°W	50.00 feet	Scr. NBT
1" dia. Iron Pipe	N18°W	32.51 feet	
1" dia. Iron Pipe	North	84.63 feet	
Power Pole	S80°E	161.75 feet	
Metal Survey Sign Post	North	4.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Scp. 08, 1997

524