

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Reestablishment  
Four Group Under Act 345 Of  
P.A. Of 1990 On 10/31 1997  
Mc Davis RLS  
Chairman

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>38</u> N R <u>27</u> W	<u>L-06</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

REGISTER OF DEEDS  
MENOMINEE COUNTY  
97 NOV 21 PM 3:18  
526  
DKS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Sept 08, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established; monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	10		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Harvey Mellen - B.T.'s - Tamarack, 12" - N03°E - 11 lks.; Tamarack, 10" - N11°W - 12 lks. All original evidence for this corner has been destroyed by logging activities.
- 1978: L.C.R.C No. 179 by Robert Perkins (RLS No. 12027) shows an Iron Pin at Post 2620.1' South of the Section Corner.
- 1982: L.C.R.C. No. 553 by James H. Moore (RLS No. 28423) states he accepted corner used by Robert Perkins in L.C.R.C. No. 179. Found Iron Pin and cedar post. B.T.'s - Cedar, 6" - N34°W - 47.2'; Cedar, 6" - N66°E - 17.65'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 3/4" dia. x 2.4' Iron Eye Bolt and old Cedar Post in a cedar swamp. The position of this monument matches well with the distance to the NE Corner of Section 14, as shown in L.C.R.C. No. 179. We also recovered a Cedar B.T. - N66°E - 17.65 feet as described in L.C.R.C. No. 553. This corner has been used by local surveyors for over 19 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 3/4" x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

10" dia. Cedar (Ex. B.T.)	N66°E	17.65 feet	Scr. NBT
6" dia. Cedar	S01°E	58.32 feet	Scr. NBT
6" dia. Blue Spruce	N88°W	43.32 feet	Scr. NBT
10" dia. White Ash	N32°W	41.92 feet	Scr. NBT
Metal Survey Sign Post	North	0.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Sept 25, 1997



526