

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Fear Group Under Act 345 Of
P.A. Of 1990 On 10/31 199 2

Mr. David RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T8N R 27W</u>	<u>I-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

97 NOV 21 PM 3:18
 REGISTERED
 5-28, 865

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Luca, in a field survey on Aug. 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 1852: Original Survey by Harvey Mellen - B.T.'s - Hemlock, 20" - N49°E - 20 lks.; Hemlock, 24" - S20°W - 25 lks. All original evidence for this corner has been destroyed by City Street improvements.
 1987: L.C.R.C. No. 900 by Charles F. Clark, RLS No. 25836, states "Found 1-1/4" square head bolt in 6" conc. cylinder similar to others established by the Wisconsin Land & Lumber Co. (Book 2 R.C., Page 552). Location checks well with plat improvements. Witnesses: 4" Maple - S25°E - 16.48'; 6" Maple - S80°W - 40.43'; SW Cor. red brick Bldg - N36°E - 105.88'; SE Cor. Back Forty Bar - N44°W - 160.37'; c/c & NW RR main track - S20°W - 61.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We identified this corner from a 1 inch square head iron bolt in a 6 inch diameter concrete cylinder approximately 12 inches below the surface of a gravel parking area, and N20°E, 61.8 feet from the centerline of the Chicago and Northwestern Railroad main track. We also recovered all 4 witnesses as described in L.C.R.C. No. 900. This corner has been accepted and used by local surveyors for over 40 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted existing 1 inch square head iron bolt in 6 inch diameter concrete cylinder:

6" dia. Maple (Existing B.T.)	S25°E	16.48 feet
8" dia. Maple (Existing B.T.)	S80°W	40.43 feet
SW Corner red brick building (Ex. Wit.)	N36°E	105.88 feet
SE Corner of Bar building (Ex. Wit.)	N44°W	160.37 feet
Metal Survey Sign Post	S18°W	52.5 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Luca
Surveyor's Michigan License No. 26461

Date Sep. 08, 1997