

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. of 1990 On 12/30, 1997
Mr. Davis RLS
 Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code #

1. Public Land Survey

T 38N R 27W M-02
 T 38N R 26W (A-02)

2. Property Controlling
 in Section

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

REGISTERED LAND SURVEYOR
 97 DEC 30 PM 4:08
 614 BLS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 (SAME AS CORNER A-02 T38N-R26W)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on Nov. 07, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by H. Brevort - B.T.'s - Cedar, 4" - N63°W - 16 lks.; Fir, 6" - S53°W - 09 lks. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set a notched base county monument at an ancient fence corner shown to me by Gary Savord a long time resident who states this has always been accepted as the corner position. This position fits well with a GLO terrain call to a swamp edge 1 chain to the South and measures 2644.30 feet North of the SE Corner of Section 6 (M-3), and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

8" dia. Cedar	N42°E	23.75 feet	Scr. NBT
7" dia. Cedar	South	11.85 feet	Scr. NBT
8" dia. Cedar	N79°W	17.16 feet	Scr. NBT
9" dia. Cedar	N19°W	18.97 feet	Scr. NBT



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1997
 Surveyor's Michigan License No. 26461

614