

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/30 1998
Chairman

For corners in

MENOMINEE
(County)

Located In: Corner Code #

- 1. Public Land Survey T38N R 28W G-09
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD
99 JAN -6 AM 8:56
PAGE # 731 BKS-
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, William Lenca, in a field survey on Feb. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column G and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

1849: Original Survey by James H. Mullett - B.T.'s - Beech, 6" - S71°W - 24 lks.; Beech, 6" - N14°W - 24 lks. All original evidence for this corner has been destroyed by farming activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set this corner in an ancient rock fence North - South and at a proportionate distance between the West 1/4 Corner of Section 22 and the West 1/4 Corner of Section 27, T38N-R28W. There are large fields on all sides of this corner with common ownership. The only occupational evidence is an ancient North - South Fence and tree line. The measurements to the 1/4 Corners half a mile North and half a mile South are 2622.50 feet. This location is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

- 18" dia. Basswood North 65.92 feet Scr. NBT
24" dia. Elm South 53.90 feet Scr. NBT
Metal Survey Sign Post East 0.55 feet
Nothing else nearby



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by [Signature]
Surveyor's Michigan License No. 26461

Date Dec. 23, 1998