

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Four Group Under Act 345 Of  
P.A. Of 1990 On DEC 16 1994  
*Mr. Henry RLS*

For corners in  
MENOMINEE  
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>38N</u>	R	<u>28W</u>	I-06
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

ACTING Chairman  
BARBARA MORRISON  
REGISTER OF DEEDS  
CORNER # 153 BK 4  
DEC 27 AM 10:45  
RECEIVED FOR RECORD  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca, Oct. 11 1994

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1849: Original Survey by James H. Mullett - B.T.'s - Hemlock, 15" - S52°W - 13 lks; Hemlock, 15" - N32°E - 13 lks. No original evidence for this corner was recovered.
- 1964: L.C.R.C. No. 494 (Vol. 3) by Neal Sperhake, Surveyor for Kimberly Clark Corp., refers to this corner as being an iron pipe in the center of an old county road right of way, 40.08 chains south of corner I-5 (NE Corner of Sec. 15).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a large angle iron in line with the extension of the centerline of a county road to the north and in line with an ancient fence running East. The measurement to the Section Corner 1/2 mile North (I-5) is 2643.66 feet compared with Sperhake's distance of 2645.3 feet (40.08 chains). We searched the area with a metal detector, but were unable to locate the iron pipe described in L.C.R.C. No. 494. It appears from record distances and occupation that the iron pipe was replaced with the angle iron. We accepted the angle iron as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-1/2" x 30" Alum. Pipe/3-1/4" dia. Alum. cap stamped for corner location:

12" dia. Maple	N14°E	46.84 feet	
8" dia. Maple	N90°E	63.37 feet	
16" dia. Maple	S22°E	41.15 feet	Scr. NBT
4" dia. Maple	N70°W	47.17 feet	
Survey Sign Post	S63°W	1.1 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 14, 1994  
Surveyor's Michigan License No. 26461

153