

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Fee Group Under Act 345 Of
P.A. Of 1990 On DEC 16 1994
Mrs. Smith, RLS

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>38N</u> R <u>28W</u>	I-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
DEC 27 AM 10:45
154 BK. 9
BARBARA MORRISON
REGISTER OF DEEDS
MICHIGAN 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca

Oct. 11 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1849: Original Survey by James H. Mullett - B.T.'s - Tamarack, 10" - S23°E - 50 lks; Tamarack, 10" - S61°E - 31 lks. All original evidence for this corner has been destroyed by County Road improvements.
1964: L.C.R.C. No. 500 (Vol. 3) by Neal Sperhake, Surveyor for Kimberly Clark Corp., established a Witness Corner 20 feet South of the corner location. He describes the W.C. as a 1" Iron Pipe 3' long with Alum. cap denoted "KIMBERLY-CLARK CORP. - TIES: Cedar, 8" - N11°W - 84.5 lks; Cedar, 6" - S30°W - 59 lks; Cedar, 10" - S68°E - 32 lks. He states that the corner was established in the centerline of an East - West County Road and in line with an old fence running south.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Railroad Spike in the centerline of an East - West County Road and in line with an old fence line running South. The Railroad Spike is 20 feet North of the Witness Corner described in L.C.R.C. No. 500. This corner has been used by local surveyors for at least 30 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-1/2" x 30" Alum. Pipe/3-1/4" dia. Alum. cap stamped for corner location:

5" dia. Cedar	N35°E	29.41 feet	Scr. NBT
14" dia. Tamarack	S33°E	68.01 feet	Scr. NBT
14" dia. Tamarack	S68°W	59.47 feet	Scr. NBT
12" dia. Cedar	N44°W	72.05 feet	Scr. NBT
Survey Sign Post	S00°W	20.4 feet	
Witness Corner	S00°W	20.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 14, 1994

Surveyor's Michigan License No. 26461

154