

APR 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/30, 1998
Mr. Davis PLS
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey | T <u>38</u> N R <u>28</u> W | <u>I-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

RECEIVED FOR RECORD
99 JAN -6 AM 8:56
PAGE # 740 BK 5
BARBARA MORRISON
REGISTER OF DEEDS
MEMPHIS, TN 38103

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, William Lenca, in a field survey on Nov., 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1849: Original Survey by James H. Mullett - B.T.'s - Hemlock, 12" - N45°W - 16 lks.; Sugar, 15" - S65°W - 16 lks. All original evidence for this corner has been destroyed by county road improvements.
1964: L.C.R.C. No. 499 (Vol 3) by Neal Sperhake refers to this corner as a reference in placing the S1/4 Corner of Section 26, T38N-R28W. The corner position is described as the intersection of the centerlines of county roads running north, south, east and west.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found no evidence of corner restoration at this location, so we re-set the corner in line with county road centerlines running North - South and East - West. We measured the distance from this corner East to the corner monumented in L.C.R.C. No. 499, and found that our measured distance of 2591 feet matched very closely with Sperhake record distance of 2591.8 feet. We accepted this location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

- | | | | |
|---|-------|------------|----------------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N50°E | 45.20 feet | 1' N. of P.P. |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S41°E | 51.69 feet | 1' S. of Rd. Sign |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S60°W | 60.16 feet | 3.3' S. of Cable Box |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N44°W | 47.02 feet | 1' W. of Cable Box |
| Metal Survey Sign Post | East | 33.8 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 29, 1998

