

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Menominee
(County)

Located in: Corner Code #

1. Public Land Survey
T___ R___
T___ R___
T___ R___
T___ R___

2. Property Controlling
in Section S 29 T 39N R 25W 15
S___ T___ R___

3. Miscellaneous
Property in Sec. S___ T___ R___
S___ T___ R___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 02 1996

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(15) West One-sixteenth corner common to Sections 29 and 32. 1980: US Dept. of Interior, Bureau of Land Management. Set 2 1/2 inch aluminum pipe with cap stamped to identify corner witnessed by: Cedar 5 N16E 39 1/2 lks. (X,BT); Cedar 6 S23E 10 1/2 lks. (W1/16 S32, BT).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15) Found monument and witnesses as described by the Bureau of Land Management. Trees marked as described and tagged with aluminum signs stamped with bearing and distance to monument. Monument in place and in excellent condition. Distances to witnesses check (NE BT rec-39.5 lks 26.1 ft. meas- 26.1 feet; SE BT rec-10.5 lks 6.9 feet meas- 7.0 feet). Accepted monument as found and marked two additional witnesses. Notch was placed in BLM witnesses to obtain a new distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) BLM monument
#6" Cedar N19E 25.7' (X,BT)
#8" Cedar N68E 25.2' (1/16S,BT)
#8" Cedar S18E 6.3' (W1/16 S32,BT)
7" Cedar S49W 12.25' (1/16S,BT)
#BLM witness. All trees are blazed, described and painted. BLM witnesses have aluminum sign. Measurements are to notch in butt blaze, bearings are magnetic.



Signed by Paul R. Bressette Date 1-7-97
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division