

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 9/25 1996  
Ma Davis RLS  
 Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE  
 (County)

Located in: Corner Code #

1. Public Land Survey T40N R 25W G13  
 T    R        
 T 39 R 25 (G-1)  
 T    R      

2. Property Controlling in Section S    T    R     
 S    T    R   

3. Miscellaneous Property in Sec. S    T    R     
 S    T    R   

REGISTERED FOR RECORD  
 96 OCT - 7 PM 3:23  
 PAGE # 337 B.H.Y.  
 REGISTERED FOR RECORD  
 REGISTERED FOR RECORD  
 REGISTERED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 (SAME AS CORNER G01 T39N-R25W).

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on Aug. 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1848: Original Survey (Township Boundary) by James H. Mullett - B.T.'s - Beech, 8" - N23°W - 08 lks; Birch, 18" - N58°E - 23 links. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 This corner was set in accordance with long standing lines of occupation as follows: The centerline of a county road running North-South, an ancient fence line running West and an old rock fence running East. This position was accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

6" dia. Cedar	N24°E	26.52 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S90°E	18.05 feet	
12" dia. Maple	S40°W	31.65 feet	Scr. NBT
7" dia. Maple	N39°W	38.49 feet	Scr. NBT
Metal Survey Sign Post	East	18.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Aug. 30, 1996  
 Surveyor's Michigan License No. 26461

327