

# SURVEY & REMONUMENTATION

APR 24 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On Dec. 9, 1994  
*William J. ...*  
Chairman

For corners in  
MENOMINEE  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 39 N R 25 W	G-4 (G-5)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 94 DEC 27 AM 10:45  
 PAGE # 148 BK 4  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49858  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims G-4 [W1/4 COR SEC 10] G-5 [SW COR. SEC 10]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- G-4 [W1/4 COR S.10] G. ADAIR D.S. - 1852 - WOOD POST (SUGAR 14°-N47°W-0.29 CHAINS) (BEECH 07°-S74°E-0.11 CHAINS)  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.
  - G-5 [SW COR S.10] G. ADAIR D.S.-1852-WOOD POST (SUGAR 16°-N66°E-0.14 CHAINS) (BEECH 15°-S87°W-0.20 CHAINS)  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- G-4 [W1/4 COR S.10] FOUND IN PLACE A 1" SOLID IRON (AXLE SHAFT) IN APPROX C/L OF CO. RD. NORTH & IN LINE WITH ANCIENT FARM FENCE LINES E. & W. THIS MONUMENT PLACED BY PERSONS UNKNOWN. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.
  - G-5 [SW COR S.10] NO EVIDENCE OF ORIGINALS FOUND - RESET CORNER AT JUNCTION OF FENCE LINES N,S, & W. (NOW DOWN AND IN POOR CONDITION) ACCEPTED THIS LOCATION AS BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-4 SET OVER EXISTING MONUMENT A BERNTSEN AINB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.
 

POWER POLE	FIRE NO. SIGN POST	SURVEY MONUMENT SIGN POST	CORNER FENCE POST
N79°W	N30°W	S63°E	S84°E
35.35' (TO FACE)	24.30' (TO FACE)	19.17' (TO FACE)	28.80' (TO FACE)
  - G-5 SET A BERNTSEN AINB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.
 

BASSWOOD 10"	IRONWOOD 6"	MAPLE 6"	SURVEY MONUMENT SIGN POST
S70°W	N14°W	N72°E	S24°E
6.93'	20.52'	12.35'	3.77' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/94  
 Surveyor's Michigan License No. 16926