

P.A. of 1990 On 9/25 19926

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

McDowd RLS
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

1. Public Land Survey

T40N R 25W H-13
T39 R 25 H-1 ✓
T R
T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

RECEIVED FOR RECORD
96 OCT -7 PM 3:24
339 BK 1
REGISTER OF DEEDS
MICHIGAN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

(SAME AS CORNER H-01 T39N-R25W)

I, William Lenca, in a field survey on Aug 12, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey (Township Boundary) by James H. Mullett - B.T.'s - Cedar, 24" - N38°E - 18 lks; Sugar, 14" - N42°W - 15 links. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner was re-set in line with an ancient fence line running West and in line with the centerline of a county road running East, and at a single proportional measurement between the Southeast Corner and the Southwest Corner of Section 34. The corner position thus established falls 2 feet North of a straight line between the SE Corner and the SW Corner of Section 34, and in line with the center of a county road running South. We accepted this location as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

7" dia. Cedar	N27°E	16.46 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S90°W	14.13 feet	
12" dia. Cedar	S39°E	87.64 feet	Scr. NBT
9" dia. Tamarack	S46°W	91.97 feet	Scr. NBT
Metal Survey Sign Post	S90°W	14.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 30, 1996