

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Fee Group Under Act 345 of
P.A. of 1990 On DEC. 9, 1994
W. William Jones
Chairman

For corners in

MENOMINEE <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 39 N R 25 W	H-5 (I-5)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 DEC 27 AM 10:45
PAGE # 149 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49856
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
H-5 [S1/4 COR SEC 10] I-5 [SE COR SEC 10]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, M.P. DAVIS, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- H-5 [S1/4 COR S.10] G. ADAIR D.S. - 1852 - WOOD POST (HEMLOCK 10"-N51'E-0.15 CHAINS) (YELLOW BIRCH 10"-S46"W-0.26 CHAINS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.
 - I-5 [SE COR S.10] G. ADAIR D.S.- 1852 - WOOD POST (SUGAR 15"-N22'E-0.08 CHAINS) (LYNN 22"-S61'E-0.25 CHAINS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- H-5 [S1/4 COR S.10] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN SECTION CORNERS E & W.



- I-5 [SW COR S.10] NO CORNER EVIDENCE FOUND AS ALL EVIDENCE OF CORNER POSITION APPEARS TO HAVE BEEN DESTROYED DURING ROAD CONSTRUCTION. RESET CORNER POSITION AT C/L INTERSECTION OF COUNTY ROADS N, S, E, & W. ACCEPTED THIS LOCATION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 SET A BERNTSEN A1NB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

BALSAM 7'	MAPLE 5'	SURVEY MONUMENT SIGN POST	BALSAM 5'	HEMLOCK 10"
N79°W	N32°W	S08°E	S30°E	N41°E
3.37'	20.89'	9.36' (TO BACK OF POST)	6.40'	25.81'

I-5 SET INSIDE A MON BOX A 5/8" X 18' REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

BASSWOOD 8"	APPLE 10"	SURVEY MONUMENT SIGN POST	NOTCH IN CULVERT EDGE
N63°W	N50°E	S45°E	S41°W
68.66'	54.69'	36.10' (TO FACE)	47.66'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/94
Surveyor's Michigan License No. 16926

RESIDENT WITNESS INTERVIEW

FOR CONSIDERATION IN THE REMONUMENTATION OF LAND CORNERS
IN THE STATE OF MICHIGAN, COUNTY OF MENOMINEE

TO WHOM IT MAY CONCERN:

Know by these presents: That I, MR. NORBERT BELLEFEUIL,
hereby submit testimony pertaining to the position of the NW corner of
Section 34, Town 39, Range 25, HARRIS
Township, MENOMINEE County, Michigan, and that my testimony is based on the
following facts:

That the land located in Section 34 T.39N. has been in the
Bellefeuil family since 1875, and that the above mentioned
corner was showed to me by my grandfather. The wood post
now in place is a perpetuation of the corner shown to me by
my grandfather.

I hereby certify on this 10 day of December, 19 93, that
the foregoing statement is a true representation of the existing facts known to me.

Signature: Norbert E. Bellefeuil
Norbert E. Bellefeuil
(Typed or Printed Name)

Street Address
N 17086 Bellefeuil Dr Ln
City State Zip Code
Oshtemo, Mi. 49896
Phone No. including Area Code
906-466-2177
Age/Occupation 72 - Formerly retired

I, the undersigned Licensed Land Surveyor, do hereby certify that the
foregoing statement was executed before me on this 10 day of December,
19 93.

M.P. Davis
M.P. Davis RLS No. 16926
(Typed or Printed Name)
807 Ludington Street
Street Address
EsCANABA, MI 49829
City State Zip Code
(906) 786-1755
Phone No. including Area Code