

# SURVEY & REMONUMENTATION

APR 24 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On Dec 9 199 94  
*W. J. ...*  
Chairman

For corners in  
MENOMINEE  
(County)

Located In: Corner Code ##

1. Public Land Survey	T <u>39 N</u> R <u>25 W</u>	(J-5 & K-5)
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECEIVED FOR RECORD  
 94 DEC 27 AM 10:45  
 PAGE # 146  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 HENNINGEN 42058

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat: \_\_\_\_\_  
 5. Private Claims J-5 [S1/4 COR SEC 11] K-5 [SE COR. SEC 11]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					●	●							
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 J-5 [S1/4 COR S.11] G. ADAIR D.S. - 1852 - WOOD POST (Y.BIRCH 20°-S62 1/2°W-0.22 CHAINS)  
 NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

K-5 [SE COR S.11] G. ADAIR D.S.-1852-WOOD POST (CEDAR 10°-N74°E-0.17 CHAINS) (CEDAR 16°-S80°W-0.18 CHAINS)  
 NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 J-5 [S1/4 COR S.11] NO CORNER EVIDENCE FOUND AS ALL EVIDENCE OF CORNER POSITION APPEARS TO HAVE BEEN DESTROYED DURING ROAD CONSTRUCTION. RESET S1/4 CORNER ON A STRAIGHT LINE BETWEEN SECTION CORNERS E. & W. & IN LINE WITH AN ANCIENT FARM FENCE TO SOUTH & OCCUPATION LINE TO NORTH. ACCEPTED THIS LOCATION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

K-5 [SE COR S.11] NO CORNER EVIDENCE FOUND AS ALL EVIDENCE OF CORNER POSITION APPEARS TO HAVE BEEN DESTROYED DURING ROAD CONSTRUCTION. RESET SE CORNER AT APPROX C/L INTERSECTION OF COUNTY ROADS E, W, & S. & IN LINE WITH AN ANCIENT FARM FENCE TO NORTH. ACCEPTED THIS LOCATION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 SET A BERNTSEN A1NB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 IRONWOOD 5"      IRONWOOD 6"      SURVEY MONUMENT SIGN POST      MAPLE 15"      C/L E & W CO. RD.  
 S72°E              S10°E                              N34°W              S35°W              NORTH  
 55.76'              67.32'                              22.60' (TO FACE)      72.93'              2.60'

K-5 SET A BERNTSEN A1NB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 TAMARACK 9"      POWER POLE      C/L E & W CO. RD.      SURVEY MONUMENT SIGN POST  
 S41°W              S42°E                              NORTH              NORTH  
 60.76'      49.10' (TO FACE)      0.70'                              14.16' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/94  
 Surveyor's Michigan License No. 16926

