

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-----------------------|
| 1. Public Land Survey | T <u>39 N</u> R <u>25 W</u> | <u>K-1</u> <u>K-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Approved by Menominee County
Lead Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On Dec 16 1994
William J. Free
Chairman

RECEIVED FOR RECORD
94 DEC 27 AM 10:45
PAGE # 151 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims K-3 [NE COR SEC 11] K-4 [E1/4 COR SEC 11]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-3 [N1/4 COR S.10] G. ADAIR D.S. - 1852 - WOOD POST (SUGAR 18°-N35°E-0.49 CHAINS) (HEMLOCK 14°-S62-1/2°W-0.30 CHAINS)
M. S. MCNABB - 1941 - FOUND MENOMINEE COUNTY SURVEYOR PAULSON'S IRON STAKE IN PLACE.
- K-4 [E1/4 COR S.11] G. ADAIR D.S.- 1852 - WOOD POST (CEDAR 08°-N3°W-0.22 CHAINS) (CEDAR 10°-S40°E-0.11 CHAINS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-3 [NE COR S.11] FOUND IRON PIN AT APPROX C/L INTERSECTION OF COUNTY ROADS N, E, & W AND FENCE LINE SOUTH. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.
- K-4 [E1/4 COR S.11] NO CORNER EVIDENCE FOUND. RESET CORNER MONUMENT AT FENCE CORNER E & W (NOW DOWN AND IN POOR CONDITION). THIS POSITION IS 6.12' SOUTH AND 6.42' EAST OF THE MIDPOINT BETWEEN SECTION CORNERS N & S. ACCEPTED THIS POSITION AS THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-3 SET INSIDE A MON BOX A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
RED PINE 11" SURVEY MONUMENT SIGN POST C/L E & W CO RD.
S40°W S3°W NORTH
53.62' 27.27' (TO FACE) 1.20'
- K-4 SET A BERNTSEN AINB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 7" CEDAR 7" SURVEY MONUMENT SIGN POST CEDAR 14" ASH 15"
N49°W N36°E S57°W S83°W S38°E
17.35' 10.23' 2.70' (TO FACE) 18.25' 12.75'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/94
Surveyor's Michigan License No. 16926

151