MICHIGAN DEPARTMENT OF CONSERVATION FORESTRY DIVISION

LAND CORNER RECORD

T 40 NR 25-26 W

Menomine COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 18, 19, 13, 24

DESCRIPTION OF CORNER MONUMENT 1 Pipe with 4 Brass Cap

WITNESSES TO CORNER 7 Hard Maple (S 19 NBT) S 36 E 19 Links

7 Hard Maple (S 13 NBT) N 34 W 38 Links

12 W. Ash (S 24 NBT) S 78 W 44 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at site of several old blazes on Hemlock and Cedar Trees. Found no evidence of original corner. Blazes are at least 27 years old.

Distance north and south along Township line are longer than record. Distance west 1/2 mile to 1/4 corner is 40.04 chains. Corner lies in SE edge of Pine and Hardwood timber type as noted in record notes.

Corner was placed and witnessed August 25, 1960 with C. Limpert, D. F. and Jay Bastian.
SURVEYORS SEAL

REGISTERED LAND SURVEYOR

ATE 9/14/60

Billy D. Bucker