

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <del>≠</del>
1. Public Land Survey	T <u>40N</u> R <u>25W</u>	<u>A-8, A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>40N</u> R <u>25W</u>	<u>10, 3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Paul Bressette, in a field survey on May 6, 13, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 10. South 1/16 corner common to Sections 19 and 24, 1971, Frank J. Bray, RLS. Set 1" iron pipe with 4" aluminum cap. 20" W. Pine, N10W, 31.1 ft.; 22" W. Pine S85E 36.9 ft.
- 3. North 1/16 corner common to Sections 19 and 24, 1971, Frank J. Bray. Set 1" iron pipe with 4" aluminum cap. 6" Cedar N17W 3.2 ft.; 8" Cedar S77E 2.1 ft.
- A-8. Quarter corner common to Sections 19 and 24, 1971, Frank J. Bray. Set 1" iron pipe with 4" aluminum cap. 10" Cedar N05W 4.3 ft.; 6" Cedar South 11.2 ft.
- A-9. Section corner common to Sections 19, 30, 24, and 25, 1971, Frank J. Bray, RLS. Set 1" iron pipe with 4" aluminum cap. 7" H. Maple N70E 10.0 ft.; 6" H. Maple S15E 8.1 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10. Found monument and witnesses as described. Monument found to be 3.74 ft. south and 2.06 ft. east of proper position as indicated in Bray's notes. Reset monument in correct position and witnessed.
- 3. Found monument and witnesses as described. Monument found to be 7.15' south and 1.55' east of proper position as indicated in Bray's notes. Reset monument in correct position and witnessed.
- A-8. Found monument and witnesses as described. Monument found to be 6.34 ft. south and 1.33 ft. east of proper position as indicated in Bray's notes. Reset monument in correct position and witnessed.
- A-9. Found monument and NBT's as described. Witnessed monument as found.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

- |                            |                              |                                 |
|----------------------------|------------------------------|---------------------------------|
| 10. Dept. Cons. - Aluminum | 3. DNR Monument              | A-8. Dept. Cons. - Aluminum/Cap |
| 26" W. Pine, S78E, 37.6'   | 10" Cedar, N71E, 16.9'       | 5" Cedar, N40E, 16.6'           |
| 5" Sugar, S17E, 22.5'      | 9" Cedar, S28E, 6.75'        | 7" Cedar, S02W, 17.65'          |
| 8" Cedar, S76W, 40.85'     | 10" Twin Cedar, S32W, 41.85' | 5" Cedar, S85W, 13.6'           |
| 24" W. Pine, N08W, 26.65'  | 8" Cedar, N16E, 6.15'        | 6" Cedar, N10W, 6.45'           |

- A-9. DNR Monument
- \*9" Sugar, N73E, 9.75' to face
- \*9" Sugar, S13E, 7.95' to face
- 5" Sugar, S64W, 28.1'
- 5" Sugar, N02W, 53.9'

Signed by Paul R. Bressette

Date 8-13-92

Surveyor's Michigan License No. 37270

