

RECEIVED

AUG 17 1992

RECREATION DIVISION  
DEPT. OF NATURAL RESOURCES

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County)	Located In:	Corner Code #
1. Public Land Survey	T 40N R 25W	B-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 40N R 25W	4,6,5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Paul Bressette, in a field survey on August 3, 4, 5, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	•	•	20	21	22	23	24						
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-8. Witness corner for center 1/4 corner of Section 19. Not set in original survey. No evidence of subsequent establishment.

4. Northwest 1/16 corner of Section 19. Not set in the original survey. No evidence of subsequent establishment.

6. Northeast 1/16 corner of Section 19. Not set in the original survey. No evidence of subsequent establishment.

5. North 1/16 corner of Section 19. Not set in the original survey. No evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-8. Corner established 2.00 feet west of center quarter corner on the East-West quarter line of Section 19. Center quarter corner established at intersection of North-South and East-West Quarter lines. Corner position occupied by 12" beech, blazed on 4 sides and scribed C1/4 S.19

4. Corner established at the intersection of the North and West 1/16 lines of Section 19.

6. Corner established at the intersection of the North and East 1/16 lines of Section 19.

5. Corner established mid-point and on line between the North and center quarter corners of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-8. DNR Monument	4. DNR Monument	6. DNR Monument	5. DNR Monument
8" Sugar, N54E, 24.3'	6" Red Maple, S76E, 18.6'	8" Cedar, N69E, 7.7'	4" Cedar, N62E, 6.65'
5" Cedar, S59E, 16.45'	8" W. Birch, S25E, 25.0'	6" Cedar, S13E, 19.0'	4" Cedar, S28E, 21.05'
6" Sugar, S64W, 21.1'	4" Spruce, S63W, 7.15'	5" Cedar, S63W, 2.9'	8" Cedar, S70W, 7.5'
6" Sugar, N11W, 15.35'	6" Red Maple, N02E, 27.55'	6" Cedar, N04E, 18.15'	5" Cedar, N61W, 30.0'

Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date 8-13-92

