

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 9/25 19996
Mc Davis RLS
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>25W</u>	<u>I-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD
 96 OCT -7 PM 3 24
 PAGE # 340 BK. 4
 BARBARA MORRISON
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on Aug. 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M		
1															
2	6			5			4			3			2	1	
3															
4	7						8			9			10	11	12
5															
6	18												15	14	13
7															
8	19												21	20	19
9															
10	30												28	27	26
11															
12	31												33	32	31
13															

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Harvey Mellen - B.T.'s - Hemlock, 14" - N67°E - 07 lks; Hemlock, 12" - S81°W - 11 links. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

An old squared wood post was found at the corner of ancient fences running North - South and East. This position fits well with measurements to the Northwest Corner and the Southeast Corner of Section 34, and fits with GLO call to swamp edge 1 chain (66 feet) East. There is remnants of a badly decayed Hemlock stump fitting the original B.T. bearing N67°E - 7 links, however, due to the state of decay, we were unable to distinguish any blazes or scribe marks. We accepted the position of the old squared wood post as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:



14" dia. Cedar	N05°E	46.85 feet	Scr. NBT
12" dia. Cedar	S89°E	28.63 feet	Scr. NBT
5" dia. White Spruce	S02°W	13.98 feet	Scr. NBT
14" dia. Cedar	N62°W	49.62 feet	Scr. NBT
Carsonite Marker	West	1.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Aug. 30, 1996