

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR. 26. W.

Menominee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22, 23, 26 and 27.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 5" H. Maple S 50 E 17 Links, marked S 26 NBT

5" H. Maple N 1 E 24 Links, marked S 23 NBT

9" W. Ash N 88 W 29 1/2 Links, marked S 22 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from probable line tree, a 40" W. Pine, which was noted 7 Links North of corner.

Checked distances South and East to swamp. Corner on old cutting line to South. Distance checks to good corner 1 mile East.

Corner lies 109 Links North of line from East.

Corner was placed and witnessed with C.L. Impert, District Forester on 6 November 1958.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED \_\_\_\_\_ Billy D. Buckler \_\_\_\_\_ DATE 4-17-59  
REGISTERED LAND SURVEYOR