

L

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR. 26 W. . .

----- Menominee ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 23 and 24 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER 7" Cedar S 46 W 14 Links, marked 1/4 S NPT.

6" Cedar S 51 E 11 1/2 Links, marked 1/4 S NBT.

6" Cedar N 5 W 19 Links, marked 1/4 S NBT.

Bearings read direct. There is considerable local attraction in area.

Corner lies 29 Links North and 29 Links West of 40.27 1/2 ch. marker from North.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Tamarack B.T. bearing S 69 W, 23 Links.

Tree down, badly rotted, overgrowth in scribe marks very plain.

Corner lies in swamp.

Corner was placed and witnessed with C. Limpert, District Forester, on 6 November 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 4-17-59
REGISTERED LAND SURVEYOR -----