

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 NR. 26 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13, 14, 23 and 24.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 9" W. Pine S 25 W 17 Links, marked "S 23 NBT"

8" W. Pine S 54 E 23 Links, marked "S 24 NBT"

7" Cedar N 36 E 29 Links, marked "S 13 NBT"

8" Cedar N 42 W 15 Links, marked "S 14 NBT"

Note: Local magnetic attraction is strong. Declination = 40° west.  
Bearings to witnesses have been corrected.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was replaced from one Cedar B.T. bearing S 51 W, 48 Links. Cedar is in poor condition.

Found several stakes and blazes at corner.

Found by C. Limpert, District Forester.

Corner was placed and witnessed on 22 January 1958.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
Billy D. Buckler DATE 4-29-59  
REGISTERED LAND SURVEYOR