

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Menominee COUNTY  
T 40 N R'S 25 & 26 W

DESCRIPTION OF CORNER Section corner for Sections T40N 24/19 T40N  
R26W 25/30 R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/12/71 F. J. Bray

WITNESSES TO CORNER..... 7" H. Maple (S. 19) (NBT) N 70°E, 10.0'



6" H. Maple (S. 30) (NBT) S 15°E, 8.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by proportioned measurement between 1/4 corner 1/2 mile to the south and the section corner 1 mile to the north. Distances to section corners to the east and to the west check well.

No original evidence was found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 6/8/71  
REGISTERED LAND SURVEYOR  
Frank J. Bray

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68