

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Menominee COUNTY
T 40 N R 26 W

DESCRIPTION OF CORNER 1/4 corner for Sections $\frac{26}{35}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/21/71

WITNESSES TO CORNER..... 6" B. Cherry (1/4 S) (NBT) N 64°W, 13.3'



9" B. Cherry (1/4 S) (NBT) S 17°W, 12.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between the section corners to the east and to the west. No original evidence was found. Squared wood stake on an old random line approximately 1 chain to the north.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

6-23-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68