

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Menominee COUNTY


T 40 N R's 25 & 26 W

DESCRIPTION OF CORNER Section corner for Sections T40N 25/30 T40N
R26W 36/37 R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/10/71 F. J. Bray

WITNESSES TO CORNER..... 18" Hemlock (S. 25 NBT) N 15° W, 14.9'



24" W. Pine (S. 31 NBT) S 27° E, 20.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by placing to conform with land calls found in the original notes. Distance to the 1/4 corner to the north checks well.

Distance to town corner to the south is short. Swamp edges to the east and west check fairly well. No original evidence was found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 6-23-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68