

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S <u>25</u> T <u>40N</u> R <u>26W</u>	<u>5</u>	_____
	S <u>25</u> T <u>40N</u> R <u>26W</u>	<u>11</u>	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

11 Nov 02 1999
 5 Oct 14 1999

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (5) North One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.
- (11) Southwest One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (5) Corner position established mid-point and on-line between the north and center quarter corners of Section 25.
- (11) Corner position established at the intersection of the south and west one-sixteenth lines of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (5) DNR monument
12" Cedar N21E 29.15' (1/16S, BT)
10" Cedar S78E 51.75' (1/16S, BT)
08" Cedar S30W 26.35' (1/16S, BT)
14" Cedar N51W 28.3' (1/16S, BT)
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic. | (11) DNR monument
16" Hemlock N83E 28.75' (1/16S, BT)
14" Sugar S10E 30.9' (1/16S, BT)
06" Cedar S71W 43.45' (1/16S, BT)
07" Cedar N73W 12.0' (1/16S, BT)
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic. |
|--|--|



Signed by *Paul R. Bressette*
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division