

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>25</u> T <u>40N</u> R <u>26W</u>	<u>12</u>	
	S <u>25</u> T <u>40N</u> R <u>26W</u>	<u>13</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 13 1999

I, Paul R. Bressette, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12) South One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.
- (13) Southeast One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12) Corner position established mid-point and on-line between the south and center quarter corners of Section 25.
- (13) Corner position established at the intersection of the south and east one-sixteenth lines of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------------|--------------------------------|
| (12) DNR monument | (13) DNR monument |
| 05" Cedar N86E 19.8' (1/16S,BT) | 6" Cedar N65E 6.6' (1/16S,BT) |
| 10" Cedar S07E 39.2' (1/16S,BT) | 8" Cedar S44E 23.1' (1/16S,BT) |
| 07" Cedar S43W 16.8' (1/16S,BT) | 8" Cedar S76W 10.8' (1/16S,BT) |
| 05" Cedar N03W 5.4' (1/16S,BT) | 5" Cedar N62W 11.3' (1/16S,BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division