

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>25</u> T. <u>41N</u> N. S., R. <u>25W</u> E. W.		<u>8, 9, 3.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8) West 1/16 cor. on the E-W 1/4 line of Section 25. Not prev. est.
- 9) East 1/16 cor. on the E-W 1/4 line of Section 25. Not prev. est.
- 3) N 1/16 cor. on the west sec. line of Section 25. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8) Set M.P.O.L. betw. the west 1/4 cor. and the center of Section 25.
- 9) Set M.P.O.L. betw. the E 1/4 cor. and the center of Section 25.
- 3) Set M.P.O.L. between the W 1/4 cor. and the NW sec. cor. of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------|--------------------------|--------------------------|
| 8) DNR Monument | 9) DNR Monument | 3) DNR Monument |
| 5" cedar S44°E, 16.1' | 7" cedar S15°E, 25.8' | 5" cedar S33°E, 20.25' |
| 5" cedar N87°W, 13.75' | 7" cedar S71°W, 12.15' | 5" cedar N51°E, 17.45' |
| 5" cedar N41°W, 9.9' | 7" hemlock N1°W, 17.75' | 4" cedar N5°W, 17.5' |
| 5" cedar N79°E, 5.7' | 10" hemlock N63°E, 3.55' | 4" cedar S75°W, 10.55' |
| Decl. 17° west. Bearings | | Decl. 10° West. Bearings |
| shown are compass readings. | | shown are compass read. |

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: