

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>41N</u> N. S., R. <u>25W</u> E. W.		<u>L-9, L-10, L-11.</u>
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

*MEMORIAL  
CO*

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 1, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9) North ¼ cor. of Sec. 25. Wood post. Cedar 12S52°E6. Cedar 8N42°W26.
- 10) Center of Sec. 25. Not prev. est.
- 11) South ¼ cor. of Sec. 25. Wood post. Sugar 10-S40W-22 Lks. Hemlock 14-N50E-30 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9) Set M.P.O.L. betw. the NE and NW sec. cors. of Sec. 25.
- 10) Set at the intersection of the N-S & E-W ¼ lines of Sec. 25.
- 11) Set M.P.O.L. betw. the SE and SW sec. cors. of Sec. 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                         |                         |                              |
|-------------------------|-------------------------|------------------------------|
| 9) DNR Monument         | 10) DNR Monument        | 11) 1" pipe, 4" alum. cap.   |
| 5" cedar N37°E - 21.4   | 10" cedar S66°W - 43.3' | 9" cedar N38°E - 11.7'       |
| 4" cedar N 5°W - 20.6'  | 13" w.pine N58°W - 8.2' | 5" sugar maple S43°E - 29.7' |
| 5" cedar S63°W - 14.15' | 8" r.maple S6°E - 30.0' | 7" hemlock S62°W - 29.1'     |
| 4" cedar S56°E - 9.75"  | 8" cedar S22°E - 44.7'  | 5" sugar maple N22°W - 29.3' |

All bearings are compass readings. Decl. is 7° West.

SIGNED BY

*David B. Babbitt*

DATE

*1-16-85*

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: