

MEMORANDUM

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41N</u> <sup>N.</sup> S., R. <u>25W</u> <sup>E.</sup> W.	<u>K-9, K-10</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W.	_____
4. LOT NO. _____	, RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 1, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 K-9) NW cor. sec. cor. of Sec. 25. Wood post, cedar 14S35<sup>0</sup>E 11, cedar 14N25<sup>0</sup>W 12.  
 K-10) West 1/4 cor. of Sec. 25. Wood post, cedar 14S48W 23 Lks, fir 12 N36E 27 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 K-9) Set by record distance to stream crossings North-West and East, which are very definite, based on increment borings of trees on riverbank; river has moved very little, if any, since original survey. Record measurements to stream are North 0.22 chs.--West 0.50 chs. and East 5.43 chs.

K-10) Set M.P.O.L. betw. the NW and SW sec. cors. of Sec. 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 K-9) 1" pipe, 4" alum. cap.  
     5" cedar N78<sup>0</sup>E 20.2'  
     5" cedar S41<sup>0</sup>E 16.65'  
     5" cedar S32<sup>0</sup>W 13.35'  
     5" cedar S68<sup>0</sup>W 9.25'  
 Decl. = 10<sup>0</sup> West.  
 Bearings shown are compass readings.

K-10) D.N.R. Monument  
     9" cedar N35<sup>0</sup>W - 13.5'  
     15" cedar N80<sup>0</sup>E - 14.7'  
     8" cedar S31<sup>0</sup>E - 27.4'  
     11" cedar S30<sup>0</sup>W - 26.2'

SIGNED BY David B. Babbitt DATE 1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_