

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Menominee	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S 26 T 41N R 25W S _____ T _____ R _____ S _____ T _____ R _____	5 _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Jeremy J. Pipp, in a field survey on 12/28/2011AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(05) Center-North One-Sixteenth corner of Section 26. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(05) Corner position established mid-point and on-line between the Center One-Quarter corner and the North One-Quarter corner of Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(05) DNR monument
 7" Cedar N60E 9.83' (1/16S,BT)
 7" Cedar S29E 5.78' (1/16S,BT)
 7" Cedar S27W 10.16' (1/16S,BT)
 7" Cedar N41W 20.86' (1/16S,BT)
 All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by [Signature]
 Surveyor's Michigan License No. 50447

July 16, 2012

For the Michigan Department of Natural Resources, Office of Land and Facilities