

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T~~41-42~~ NR ~~25-26~~ W

M e n o m i n e e COUNTY

DESCRIPTION OF CORNER Section corner for Sections 6, 1, 36, 31 also a Township corner.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Hard Maple (S 1 NBT) S 51° W 53 1/2 Links

10" Hard Maple (S 31 NBT) S 47° E 44 1/2 Links

10" Iron Wood (S 36 NBT) N 34° W 43 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at old wood post set by unknown surveyor.

Found old turnout at site of NE B.T. also found a Hard Maple 24" bearing N 75° W 34 1/2 Links This tree is scribed (R 26 W S 36) Found no record of this tree.

This tree was marked when about 8" in diameter.

Corner was placed and witnessed August 12, 1960 with E. Dahlvik, Sawyer-Soll Timber Company and J. Bastian, Escanaba.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/14/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler