

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Menominee
(County)

Located In: Corner Code #

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S 13	T 41N	R 26W 6
	S 13	T 41N	R 26W 9
3. Miscellaneous Property in Sec.	S 13	T 41N	R 26W 13
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

13 May 25, 1995
9 May 24, 1995

I, Paul R. Bressette, in a field survey on 6 June 06, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (6) Northeast One-sixteenth corner of Section 13. Not set in original survey, no evidence of subsequent establishment. Old wood post and location poster about 100 feet SE of monument.
- (9) East One-sixteenth corner of Section 13. Not set in original survey, no evidence of subsequent establishment.
- (13) Southeast One-sixteenth corner of Section 13. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6) Corner position established at the intersection of the North and East One-sixteenth lines of Section 13.
- Corner position established mid-point and on-line between the East and Center Quarter corners of Section 13.
- (13) Corner position established at the intersection of the South and East One-sixteenth lines of Section 13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------|-----------------------|-----------------------|
| (6) DNR monument | (9) DNR monument | (13) DNR monument |
| 13" Sugar N22E 49.85' | 06" Spruce N37E 42.9' | 05" Sugar N86E 28.5' |
| 07" Sugar S57E 40.7' | 08" Sugar S11E 6.05' | 10" Sugar S30E 42.35' |
| 08" Sugar S37W 30.65' | 10" Sugar S47W 31.0' | 09" Sugar S89W 50.7' |
| 11" Cedar N53W 51.55' | 08" Sugar N27W 26.65' | 09" Sugar N50W 59.9' |



Paul R. Bressette Date 11-15-95
37270