

APR 06 1999

PA. Of 1998 On 12/14, 1998
William A. Wanic P.S.
Surveyor

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 41 N R 26 W L-09
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
93 DEC 14 PM 3:23
PAGE # 690 BK 5
REGISTERED LAND SURVEYOR
WILLIAM A. WANIC
MICHIGAN LICENSE NO. 26461

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on June 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by E.C. Martin - B.T.'s - Tamarack, 10" - N10°E - 14 lks.; Tamarack, 10" - S67°W - 29 lks. Most original evidence for this corner has been destroyed by logging activities.
- 1955: L.C.R.C. No. 210 by Billy D. Buckler states, "Found this corner while with C. Limpert, District Forester. Two Tamarack B.T.'s. One excellent and one fair condition." Set 1" Pipe with 4" Brass cap - TIES: Cedar, 4" - N21°E - 22 lks.; 4" Cedar - S70°E - 37 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1-1/4" Iron Pipe with a 4" brass cap set by the Michigan Department of Conservation in a location as indicated in Land Corner Recordation Certificate Number 210 by Billy D. Buckler. We also recovered the remains of one of the original Bearing Trees (Tamarack, 10" - N10°E - 9.2') down but still in good condition. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 1-1/4" Iron Pipe with 4" Brass Cap:

8" dia. Cedar	N02°E	28.77 feet	Scr. NBT
4" dia. Cedar	S74°E	15.97 feet	Scr. NBT
9" dia. Tamarack	South	18.18 feet	Scr. NBT
8" dia. Tamarack	N72°W	33.24 feet	Scr. NBT
Metal Survey Sign Post	South	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sept. 14, 1998

